



PO BOX 7663 ROCKY MOUNT, NC 27804

PHONE: 252-443-5659

FAX: 252-443-5601

NC LICENSE # 20208

ELECTRICAL LICENSE # U 28265

March 27, 2024

Warren County Schools  
Attn: Greg Tharrington

Warren County School 50 Ton  
Rooftop DX Proposal Rev 1

We are pleased to price the above project as Noted below:

1. Remove the existing condensing unit from roof, DX coil inside AHU, refrigerant piping, and all ancillary components from the existing 50-ton AHU.
2. Provide and install new 50 Ton Trane condensing unit on roof in the same location as the one removed. The new unit will be set on the existing structural supports. See attached submittal.
3. Provide and install new DX coil inside the existing AHU in the same location as the one removed. All other existing components of the AHU are to remain.
4. Provide and install all new refrigerant piping materials and ancillary components to complete the refrigerant system between the new condensing unit on the roof and the new DX coil installed inside the existing AHU. .
5. All refrigerant piping to be ACR copper material with brazed joints.
6. Provide and install Armaflex insulation on refrigerant suction line. Armaflex on roof will be covered with an aluminum jacket.
7. Connect the condensing unit on roof to the existing electrical circuit and controls.
8. No controls modifications included.
9. Start up and test operation of new DX system.

**PROPOSAL TOTAL: \$ 140,536.00**

**Exclusions:**

- There are no Contingencies or Allowances included.

Prepared by:  
Tony Morris